



**Chettinad**  
College of Engineering & Technology  
Approved by AICTE, New Delhi and Affiliated to Anna University, Chennai.

**Department of Civil Engineering**

**CE8022 – Prefabricated Structures**

**Unit III – MCQ Bank**

1. What demands for disuniting the prefabricated structures?

- a) Less weight
- b) Quality
- c) Transportation and placing of structures**
- d) Design Constraints

Answer: c

2. In the production of prefabricated structures how does the material used in construction affect the element?

- a) Material quality and economic design**
- b) Smaller members
- c) Disuniting of members
- d) Joints

Answer: a

3. What is disuniting of Structure?

- a) Dividing into panels
- b) Organizing the panels
- c) Erecting the panels
- d) Making into smaller members**

Answer: d

4. If Joint deformation in the prefabricated structures is allowed It means

- a) Allowance for joint flexibility**

- b) Allowance for stress
- c) Allowance for swaying
- D) Allowance for stress accumulation

Answer: a

5. The large reinforced concrete roofing members in prefabricated structures are

- a) Directly supported by main girders**
- b) Directly supported on panel members
- c) Two way reinforcement is provided
- d) Provided with less reinforcement

Answer: a

6. At what point in the members disuniting should be done?

- a) At minimum shear points
- b) At corners or points of minimum moments**
- c) At points of maximum moment
- d) At intersections

Answer: b

7. What is the disadvantages of disuniting of structures?

- a) Easy to transport the members from casting yard to site.
- b) Requires lesser capacity of lifting arrangements.
- c) Identifying the joint location**
- d) Require less amount of supporting arrangements

Answer: c

8. Arrange the stages of loading in the preparation of prefabricated buildings.

I-Erection stage

II- Function of individual components in a finished building

III - De-moulding and transport of the components

- a) I,II,III

b) **III, I,II**

C) I. III.II

d) II,I,III

Answer: b

9. Why should we give allowance for joint deformation?

a) To take care of the joints

**b) To take care of the deformation due to irregularities**

c) To take care of the disuniting of member

d) To take care of moments in the members

Answer: b

10. Based on load transfer the joints can be classified as

a) Tension joint

b) Compression joint

c) Flexural joint

**d) All of these**

Answer: d

11. The cross section design of wall panel depends on the requirements

**a) Sandwich type wall panels**

b) Provide insulation

c) Heavy weighted

Answer: a

12. For simple placing of members what type of joint is preferred?

a) Wet Joints

**b) Dry joints**

c) Construction joints

d) Expansion joints

Answer: b

13. The economy of cross section is measured by

- a) Shape factor
- b) Form factor**
- c) Section modulus
- d) Material

Answer: b

14. For prestressed concrete section form factor is

- a) Less than 1
- b) Equal to one
- c) 0.3 to 0.4
- d) 0.45 to 0.5**

Answer: d

15. During design of elements in prefabricated structures due consideration should be given to

- a) Quality Materials
- b) Stresses developed during handling the members
- c) Minimum factor of safety
- d) All of these**

Answer: d

16. During disuniting joints are provided at

- a) At corners or point of minimum bending moment joint**
- b) At center of member
- c) At intersections
- d) At tension joints

Answer: a

17. In places where transportation of large members is difficult what kind of fabrication is preferred?

- a) Plant prefabrication

**b) Site fabrication**

- c) Standardisation
- d) Prefabricate systems

Answer: b

18. Transportation of precast members accounts for about

- a) 20-25% of the cost of production and assembling
- b) 10-15% of the cost of production and assembling**
- c) 10-20% of the cost of production and assembling
- d) 5-15% of the cost of production and assembling

Answer: b

19. Plant fabrication is suited better for

- a) Large number of small prefabricates**
- b) Large e long panel members
- c) Standard is members
- d) Limited production

Answer: a

20. Joint flexibility indicates that

- a) Joints are rigid
- b) Relative swinging is allowed with a tolerance**
- c) Restricts movement

Answer: b

21. Bearing pads are used to resist

- a) Vertical loads**
- b) Horizontal loads
- c) Vertical and horizontal load

Answer: a

22. A connection must have ----- to avoid failure during life time

- a) **Strength**
- b) Durability
- c) Ductility

Answer: a

23. Shear wall resist lateral load.

- a) **True**
- b) False

Answer: a

24. The design considerations for the precast concrete components of a project consist of

- a) **Three**
- b) Two
- c) Four

Answer: a

25. How many basic configurations for large panel construction

- a) Four
- b) **Three**
- c) Two

Answer: b